WESTERN COOKING AREA
CHINESE COOKING AREA
EXHAUST ABOVE
EXHAUST ABOVE
85'-1"
BAGGAGE AREA
100 SF./ 1 OCC.
SHELVES
SHELVES
MAIN ELEC. ROOM
360 SF./ 2 OCC.
UTILITY ROOM
100 SF./ 1 OCC.
4'-6"
80'-4"
ELEVATOR LOBBY
450 SF.
HOUSE KEEPING
MEN'S RESTROOM
WOMEN'S RESTROOM
COVERED COLONNADE
WOMEN'S RESTROOM
MEN'S RESTROOM
BANQUET STORAGE/ PANTRY
350 SF./ 2 OCC.
FLOOR MOUNTED VERTICAL FAN COIL UNIT(TYP.)
CART
CART
CART
CORRIDOR
POOL
3,300 SF.
SWIMMING POOL (SEPARATE PERMIT)
WHIRLPOOL (SEPARATE PERMIT)
DOUBLE QUEEN 129
DOUBLE QUEEN 131
DOUBLE QUEEN 133
DOUBLE QUEEN 134
DOUBLE QUEEN 135
DOUBLE QUEEN 136
DOUBLE QUEEN 137
DOUBLE QUEEN 138
COVERED COLONNADE
SHELVES
WASHER
WASHER
DRYER
DRYER
GUEST LAUNDRY
300 SF./ 1 OCC.
EMPLOYEE BREAK AREA
IN CEILING, SEE MECH. DWG.
FITNESS GYM
670 SF./ 14 OCC.
WEIGHTS
TREADMILLS
CYCLING
LAUNDRY
950 SF./ 4 OCC.
SHELVES
ENGINEERING ROOM
330 SF./ 2 OCC.
FLOOR MOUNTED VERTICAL FAN COIL UNIT(TYP.)
STAIR 3
160 SF.
UP
LINEN CHUTE
TYPE III-A 2-HR EXTERIOR WALL ASSEMBLY W/ FIRE RETARDANT WOOD MEMBERS, TYP. SEE 11/A-8.01
PROVIDE STAND PIPE CONNECTION PER FIRE DEPT. REQ'D
PROVIDE CLASS (I) STAND PIPE IN STAIR AT THE MAIN LANDING PER FIRE DEPT. REQUIREMENT
PROPOSE TO CONVERT THIS AREA TO 8 GUESTROOMS

WALL LEGEND:

- EXISTING INTERIOR WALL TO REMAIN
- EXISTING EXTERIOR WALL TO REMAIN
- EXISTING WALL TO BE REMOVED
- NEW WALL PROPOSED

64'-2"

NORTH

PROPOSED REVISION
PARTIAL 1ST FLOOR PLAN

SCALE: 1/8" = 1'-0"

FILE: 180709SA2STE101
DRAWN: K.C.

ARCHITECT:
SIMON LEE & ASSOCIATES ARCHITECTS
simon@slarch.com
www.slarch.com
140 W. VALLEY BLVD., SUITE 215
SAN GABRIEL, CA 91776
TEL: (626) 571-8000
FAX: (626) 571-8005

PROJECT:
Holiday Inn
BUILDING REVISION
9920 VALLEY BLVD., EL MONTE CA 91731

LICENSED ARCHITECT
SHUO-TSUNG TSAI LEE
No. C 14526
Ren. 11-30-19
STATE OF CALIFORNIA

JOB NO: 180709

3 7/11/2018 REVISIONS

A-2.2